



# AIR FORCE BAL BHARATI SCHOOL

LODI ROAD, NEW DELHI – 110003 | Ph.: 011-43564950

E-mail: [afbbschool@gmail.com](mailto:afbbschool@gmail.com) | Website: [airforcebalbharatischool.in](http://airforcebalbharatischool.in)

CBSE Affiliation No.: 2730006 | DOE ID: 1924138

## TENDER NOTICE

### AIR FORCE BAL BHARATI SCHOOL, LODI ROAD, NEW DELHI-110003

1. Tenders are invited from vendors for the following work at **Air Force Bal Bharati School, Lodi Road, New Delhi** as per the details mentioned below:

Description of works	Bid/ Quotation Starting Date	Bid/ Quotation Submission Closing Date	Tender opening date	Visit for site assessment
Upgradation of Canteen	04 Jun 2024	21 Jun 2024 (Till 1100hrs)	21 Jun 2024 (1130hrs)	10 Jun to 19 Jun 24 <b>(0900hrs to 1130 hrs on working days)</b>

2. **Expectation from Bidders:** - The tenderer shall visit the site to make an assessment of the requirements including related costs.

3. The bidder has to be ESIC compliant or 4% will be recovered towards labour charges.

4. The school management reserves the right to accept or reject any or all the quotations without assigning any reason.

**Note: For any query regarding the work, please contact Principal, Air Force Bal Bharati School, Lodi Road, New Delhi.**

**COMPLETE TENDER FORM TO BE COLLECTED FROM  
SCHOOL COUNTER**



# **AIR FORCE BAL BHARATI SCHOOL**

LODI ROAD, NEW DELHI – 110003 | Ph.: 011-43564950

E-mail: [afbbschool@gmail.com](mailto:afbbschool@gmail.com) | Website: [airforcebalbharatischool.in](http://airforcebalbharatischool.in)

CBSE Affiliation No.: 2730006 | DOE ID: 1924138

## **TENDER FORM**

### **UPGRADATION OF CANTEEN**

**AT**

**AIR FORCE BAL BHARATI SCHOOL  
LODI ROAD, NEW DELHI – 110003**

<b>Date of issue of Tender Form</b>	<b>:</b>	<b>04 Jun 2024</b>
<b>Last date for submission of tender</b>	<b>:</b>	<b>21 Jun 2024 (Till 1100hrs)</b>
<b>Tender opening Date/Time</b>	<b>:</b>	<b>21 Jun 2024 (at 1130hrs)</b>
<b>Tender cost</b>	<b>:</b>	<b>Rs. 1000/- (Cash/Online)</b>

## TENDER NOTICE AND SCHEDULE OF EVENTS

1. Sealed Bids are hereby invited under two bid systems (Technical Bid and Financial Bid) from reputed and experienced firms/contractors/agency possessing valid licenses and are in the business of construction, for **Upgradation of Canteen at Air Force Bal Bharati School, Lodi Road, New Delhi-110003.**

Name of the Work	<b>Upgradation of Canteen</b>
Tender Submission Cost (Non-refundable)	Rs. 1,000/- (Cash/Online)
EMD amount to be deposited	<b>Rs. 20,000/- (Rupees Twenty Thousand Only)</b>
Completion Period	45 days
Downloading of Tender Document from school's website	<b>04 Jun 2024 onwards</b>
Last date for submission of Tender Form	<b>21 Jun 2024 at 1100hrs</b>
Postal Address for correspondence/sending bids	Air Force Bal Bharati School, Lodi Road, New Delhi - 110003
Opening of Tender	<b>Part-A Technical Bid:</b> The Technical Tender documents shall be opened on <b>21 Jun 2024</b> at 1130hrs in the presence of authorized representatives of the bidders.
	<b>PART-B Financial Bid:</b> The Financial Bid shall be opened after evaluation of the technical bids.
Contact person (for any clarifications)	<b>Principal, AFBBS</b> Tel No: 011- 43565950, 43597238 (0900hrs to 1400hrs)

2. AFBBS may issue addendum(s)/corrigendum(s) to the tender documents through the school's website. Such addendum(s)/corrigendum(s) (if any) shall also be submitted, duly stamped and signed, along with the submission of the Tenders.

**ESSENTIAL DETAILS OF SERVICES REQUIRED FOR  
UPGRADATION OF CANTEEN AT AFBBS**

**1. Schedule of Requirements:**

SI No	Item	Unit	Qty
	<b>CIVIL WORK</b>		
1	Brick work with common burnt clay FPS bricks of class designation 75 in super structure for all levels in 1:6 cement mortar ( 1 Cement : 6 coarse sand) including scaffolding, curing complete in all respect.	CUM	1
2	Providing 12-15mm average cement plaster to surface of walls, columns, piers etc., applied finish smooth and cured, complete, with mixes- 1:6 (1 cement: 6 coarse sand).	SQM	15
3	Transporting/ disposal of surplus malba from the site of work including loading unloading etc. all complete to the nearest municipal/ contractor's dump	LS	-
4	Dismantling of overhead slab of thickness 50mm	SQM	1
5	Providing and fixing MS rolling shutters of 22 g. sheet, including the cost of paint and primer	SQM	4.5
6	Removal of existing windows and grill	LS	
	<b>WOOD AND PANELLING WORK</b>		
7	Removing the existing open shelf and making new open shelf of similar design, using 18mm thick	SQM	5
8	Providing and fixing single leaf ISI marked 35mm thick flush door shutters decorative type, core of block board construction with frame of 1st class hard wood and well matched 4mm thick veneer of approved shade of make century/ green on both faces of shutters. The shutters will have cut out of size of 300x1500mm fitted with 8mm toughened glass including ISI marked necessary hardware like hinges, handles, locks etc. The rate should include the cost of melamine polish on doors and door frames by scraping/ removing the paint from existing door frame all complete.		
a	900X2100		1
9	Providing and Fixing of digital print on sunboard, as desired, with all around wooden frame in marindi wood of size 50X25mm with polishing all complete.	SQM	15
10	<b>UPVC Windows, Ventilators and Door:</b> Providing and Fixing, UPVC factory made, white color casement/sliding window and door made of extruded profiles. Profiles of frames and sash will be mitered cut and fusion welded at all corners including drilling of holes for fixing hardware and drainage of water etc., making arrangement for fixing of hardware, EPDM gasket, 1.2 ± 0.2mm thick galvanized steel profile to be inserted in required profile, frame will be fixed to the wall with 8 mm x 100 mm long fasteners, all complete as per direction of Engineer-in-charge. The Rates inclusive of 6mm toughened glass, hardware hinges and fitting etc. of make Fenesta or equivalent		
a	Window Casement (800X1200mm)	Each	7
b	Window fixed (800X600mm)	Each	7
c	Window Casement (2700X1200mm)	Each	1

d	Window fixed (2700X600mm)	Each	1
e	Door casement (800X2100)	Each	1
11	Providing and fixing of Fixed Glass partition with 8 mm thick toughened glass using fittings of make Ozone, dorma at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, ceiling etc. and making the same good with necessary fittings upto all heights including scaffolding all complete	SQM	7
12	Removal of glass of main door and replacing it with 4mm thick polycarbonate sheet of make	SQM	15
	<b>TILLING AND STONE WORK</b>		
13	Providing and fixing first quality tiles of size 600X600 mm of approved make and shades over 12mm thick CM 1:3 (1 cement :3 coarse sand) including grouting, matching to the shade of the tile	SQM	7
14	Polishing on granite work/stone work where ever required to give high gloss finish complete.	SQM	85
	<b>ELECTRICAL WORKS</b>		
15	Providing and making point wiring concealed in walls, furniture & for above false ceiling, or on ceiling, on beams shall be fixed with metal saddles & metal spacers etc., with conduits taken in slab with 20 mm dia PVC Rigid conduits 1.5 mm thick ISI mark with 2 nos. of 1.5 sq. mm. & 1 nos. of 1.0 sq. mm. FRLS type wire of make Finolex/Polycap or equivalent with modular switch of make Anchor Roma or equivalent with company made flush metal box/surface PVC box etc.		
a	One light point with 6 Amp. switch.	Each	15
b	Fan point with 6 Amp. switch. With regulator	Each	10
c	One 5 pin 6 amp shuttered socket outlet with 6 amp switch	Each	15
16	Switch and socket of 6/16 Amp of make Anchor/ Roma or equivalent with wiring of make Finolex/Polycap or equivalent from DB with 2 no of 2.5 sqmm wires and 1 no of 1.5 sqmm PVC Insulated copper conductor wire laid in 25 mm dia PVC rigid conduits ISI marked, concealed in walls, furniture & for above false ceiling, or on ceiling, on beams shall be fixed with metal saddles & metal spacers etc. all complete for power points. Contractor must visit the site to ascertain the length of required wire	EACH	5
17	Supply, installation, testing and commissioning of Surface mounted 36W LED panel light of size 2'X2' and making loop connections from existing electrical points. The rate should include cost of wiring, batten etc for loop connections and scaffolding (make Havells, Syska) all complete.	Each	8
18	Replacing old ceiling fan with new 48" high speed ceiling fan of make orient or equivalent include the cost of scaffolding all complete.	Each	6
19	Supply of wall / ceiling surface mounted 4', 18 watt LED tube light luminaries with cover all accessories as per standard item including required LED tube etc complete make Philips/Syska or equivalent	Each	4

20	Supply installation testing and commissioning of 450 mm sweep metal body heavy duty, 900 RPM Exhaust fan with guard/ shutter and mounting with all necessary arrangement	Each	3
<b>PAINTING AND POP</b>			
21	Providing and applying Plaster of Paris of make Sakarni or equivalent, punning on walls with minimum thickness of 6mm and finish the surface smooth in line and level including scraping and hacking the existing finished surfaces, scaffolding etc. complete.	SQM	300
22	Providing and applying two or more coats of plastic emulsion of make Asian paint, Dulux or equivalent and shade as approved including preparing the surface with putty priming coat etc. Complete on walls & ceilings	SQM	350
23	Scrapping the OBD/paint thoroughly from the existing surface and preparing the same with putty all over and applying one coat of primer and two or more coats of OBD of make Asian paint, Dulux or equivalent of approved shade. Work to be carried out as per the manufacturer's instruction (the rate should include the cost of scaffolding, if any) all complete	SQM	60
24	Scrapping old paint and applying 2 or ore coats of Satin finish enamel paint on table frames of make Asian paint, Dulux or equivalent and shade as approved (the rate should include the cost of scaffolding, if any) all complete	Each	
A	Size 1200X1200	Each	4
B	Size 900X1200	Each	4
C	Main entrance gate (3600x3000)	Each	1
25	Providing and fixing of panelling on walls with WPC fluted panels of size 2950X195X27mm of approved make Leben/Alutuff/murrato or equivalent and approved shade and pattern. Rate should be inclusive of all hardware fittings as required to fix the same on the wall including cover beading and fastener all complete	SQM	60
<p>The tenderer shall visit the site of work before tendering.  <b>The tenderer shall provide a written five years' warranty for workmanship, materials and installation from the date of certified completion.</b></p>			

## 2. Technical Details:

- (a) Requirement of installation: Based on School directions.
- (b) Requirement of Technical documentations: ITR, ESIC, EPF.
- (c) Warranty Period: **05 years**
- (d) Requirement of On-site/equipment inspection: Yes

3. **Two-Bid System:** In respect of two-bid system, Bidders are required to furnish clause-by-clause compliance of specifications bringing out clearly the deviations from specification, if any.

4. **Work / Construction Period:** The work should start within 07 days from the effective date of signing of contract or issuing of work order. Please note that the School can cancel Work Order unilaterally in case construction is not starting within the stipulated time. Extension

of contracted work period will be at the sole discretion of the School, with the applicability of LD (Liquidated Damages) clause.

5. **Incoterms for Delivery and Transportation:** N/A.
6. **Consignee Details:** Principal, Air Force Bal Bharati School, Lodi Road, New Delhi -03
7. **Provision of Electric Sub-Meter:** Contractor is to fix an electric sub meter in consultation with School Authorities for electric work required during execution of subject works services. Electric charges will be as per actual consumption at a flat rate of ₹8.50 plus 18% GST per unit, to be borne by the contractor. The same will be adjusted against his bills at the time of payment.
8. **Provision of Water Arrangement:** Contractor will have to arrange suitable quality of water on his own for entire work services. Under any circumstances, school will not be responsible for arrangement of water for the said work. The quality of water being used will have to be as per standard specifications. Provision for storage of water for construction purpose shall also be made by the contractor only.
9. **Quantity:** The quantity of the items indicated above is tentative and it will be entirely at the discretion of the School to place order as per its requirement.

**COMPLETE TENDER FORM TO BE  
COLLECTED FROM SCHOOL COUNTER**